# BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

**Executive Engineeer**
**Byatarayanapura Division**
**B.B.M.P., Bangalore - 92**

## DRAFT TENDER SCHEDULE

**Name of Work: Improvements to Footpath and Drains in ward no:07 Byatarayanapura**

| Sl. No. | Quantity. | Description | Unit | Rates | |
|---|---|---|---|---|---|
| | | | | In Figures | In Words |
| 1 | 1019.07 | Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 m and an average lift upto 1.5m, excavated surafce levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking clods complete as per specifications.. | Cum | 137.80 | Rupees One Hundred Thirty Seven and Eighty Paise Only |
| 2 | 32.76 | Providing and laying in position plain cement concrete of mix 1:3:6 with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration inlcuding curing for 14 days including cost of all materials labour, HOM curing, form works, scaffolding and centering complete as per specification . | Cum | 5905.51 | Rupees Five Thousand Nine Hundred Five and Fifty One Paise Only |
| 3 | 63.18 | 1:Providing and constructing granite /trap/basalt size stone masonry in foundation with cement mortar 1:6, stone hammered dressed in courses not less than 20cms hign, bond stones at two m apart in each course including cost of materials, labour, curing etc., complete as per specifications. | Cum | 4871.76 | Rupees Four Thousand Eight Hundred Seventy One and Seventy Six Paise Only |
| 4 | 28.08 | KSRRB M200-5.1: Providing and laying cement concrete of mix 1:2:4 with OPC @ 240 Kgs with 40mm and down size graded granite metal coarse aggregates @ 0.63cum and fine aggregates @0.42 cum including cost of materials, labour, HOM curing, form works scaffolding and centering complete as per MORTH section:2200 & IS 456, A) Upto 5mtr height. | Cum | 6273.8 | Rupees Six Thousand Two Hundred Seventy Three and Eighty Three Paise Only |
| 5 | 117 | Providing and fixing 25 cm thick pre cast RCC covering slab using reinforced cement concrete M 20 mix with stone aggregate 20 mm and down size including centring shuttering reinforcement and bar bending machine mixed concrete laid in layers not exceeding 15 cm thick wellcompacted cost of all materials labour curing comlete as per specification (Data Rate) | Sqm | 5418 | Rupees Five Thousand Four Hundred Eighteen Only |
| 6 | 101.25 | Providing and fixing 10cms thick pre cast RCC covering slab using reinforced cement concrete M20 mix with stone aggregate 20mm and down size including centring shuttering reinforcement and bar bending machine mixed concrette laid in layers not exceeding 15 cm thick wellcompacted cost of all materials labour curing complete as per specfications ( Data Rate Approved) | Sqm | 2337 | Rupees Two Thousand Three Hundred Thirty Seven Only |

## Name of Work: Improvements to Footpath and Drains in ward no:07 Byatarayanapura

| Sl. No. | Quantity. | Description | Unit | Rates | |
|---|---|---|---|---|---|
| | | | | In Figures | In Words |
| 7 | 1019.07 | KSRRB M100-1 Loading and unloading of stone boulder/stone aggregates/ sand/ kanker/ moorum. KSRRB M100-1:Placing tipper at loading point loading with front end loading, dumping turning for return trip, excluding time for haulage and return trip complete as per specification | Cum | 94.34 | Rupees Ninety Four and Thirty Four Paise Only |

16/02

**Executive Engineer**
**Byatarayanapura Division**
**BBMP, Bangalore - 92**

16/02

**Note:**

1 Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of quantities (refer: ITB Clause 7.2 and CC Clause 33.2)

2 Unit rates and prices shall be quoted by the Tender in Indian rupees.

3 Where there is a discrepancy between the rate in figures and words the rates in words will govern (ITB Clause

4 Where there is a discrepancy between the unit rate and the line item total resulting from multyplying the unit rate by quantity the unit rate quoted shall govern (ITB Clause 19.1(b))